

ESTIMATE

Name of Work

Berhampore Division-I, P.H. Engineering Dte.

Allied Work for Road Restoration, Laying of Balance portion of UPVC and Rising Mains at Kashipur Zone-II
PWSS under Berhampore Division-I, P.H.E. Dte.

S. No.	Description of Works/Items	Quantity	Unit	Rate	Amount
(1)	(2)	(3)	(4)	(5)	(6)=(3)x(5)
1	Dismantling all types of plain cement concrete works by mechanical means using pne Ref. It-2(a), Pg-10, PWD SOR Vol-I	140 Cum.	₹	939.00	₹ 1,31,460.00
2	Ordinary Cement concrete (mix 1:2:4) with graded stone chips (20 mm nominal size) Ref. It-33, Pg-12, Cg-3, PWD SOR Vol-I	260 Cum.	₹	5,740.13	₹ 14,92,433.80
3	Supplying, laying, fitting, fixing and jointing of UPVC pipes conforming to IS:4985-2001 N.B. i) Manufacturer's test certificate for UPVC pipe & specials to be produced before Ref. It-2, Pg-L3, PHED SOR Civil'2019				
	b) 90mm (OD)	2100 Mtr.	₹	342.00	₹ 7,18,200.00
4	c) 110mm(OD)	216 Mtr.	₹	471.00	₹ 1,01,736.00
5	d) 125mm(OD)	204 Mtr.	₹	643.00	₹ 1,31,172.00
6	Filling the pipe line with water, testing hydraulically as per I.S 3114-1965 (Article-6) in Ref. It-9, Pg-L18, PHED SOR Civil'2019				
	b) 90mm (OD)	2100 Mtr.	₹	3.60	₹ 7,560.00
7	c) 110mm(OD)	216 Mtr.	₹	3.78	₹ 816.48
8	d) 125mm(OD)	204 Mtr.	₹	3.82	₹ 779.28
9	Cleaning thoroughly the inner surface of pipe line including specials and valves by flu Ref. It-10, Pg-L19, PHED SOR Civil'2019				
	b) 90mm (OD)	2100 Mtr.	₹	0.88	₹ 1,848.00
10	c) 110mm(OD)	216 Mtr.	₹	1.08	₹ 233.28
11	d) 125mm(OD)	204 Mtr.	₹	1.24	₹ 252.96
12	Carrying CI/DI pipes with specials and valves and lowering placing in position and lay N.B: i) Any deviation from required clear cover of 1.10mtr., due to site adverse condit				
	i. 150mm dia.	1512.5 Mtr.	₹	112.00	₹ 1,69,400.00
13	ii. 250 mm.dia.	165 Mtr.	₹	164.00	₹ 27,060.00
14	Making rubber gasket joint to CI/DI pipes maintaining proper alignment level etc. by n iv) 150mm dia.	276 Each	₹	38.00	₹ 10,488.00
15	vi) 250mm dia.	31 Each	₹	64.00	₹ 1,984.00
16	Carrying charges of materials M.S. Rod, D.I. Pipe, G.I. Pipe, TW materials, C.I.Dt. Jo e) For distance (above) 25 Km.to 50 Km.	50 MT/km	₹	496.00	₹ 24,800.00
17	Labour charges for Horizontal Auger Boring through any kind of soil for road crossing 125 mm dia pipe to 100mm dia	54 Mtr.	₹	338.20	₹ 18,262.80
18	200 mm dia pipe to 150 mm dia	15 Mtr.	₹	505.40	₹ 7,581.00
19	250 mm to 300 mm. dia. Pipe	12 Mtr.	₹	765.70	₹ 9,188.40
20	Supply of GI pipe of Non TATA MAKE M	54 Mtr.	₹	664.00	₹ 35,856.00
21	150 mm dia	15 Mtr.	₹	1,036.00	₹ 15,540.00
22	Construction of Sub Base using Local Materials, spreading in uniform layers with Mot Ref. It-4.09, Pg-247, PWD SOR Vol-III	413.8125 Cum.	₹	1,545.32	₹ 6,39,472.73
23	Supply and laying of PVC/HDPE Pipe for House Service Connections including labour				

S. No.	Description of Works/Items	Quantity	Unit	Rate	Amount
(1)	(2)	(3)	(4)	(5)	(6)=(3)x(5)
	Ref. Rate Approved by SE/MC	8100 Mtr.	₹	117.00	₹ 9,47,700.00
24	Supplying of UPVC Coupler 6Kg., class – III conforming to IS : 4985 – 2000 with late:				
	c) 90 mm dia (OD)	150 Each	₹	67.00	₹ 10,050.00
25	d) 110 mm dia (OD)	30 Each	₹	99.00	₹ 2,970.00
26	Supply of CI specials as per direction of	1500 Kg(s).	₹	61.00	₹ 91,500.00
27	Ref. It-1 to 15, Pg-102 to 110, PWD SOR Vol-II				
	Supply of G. I. pipes of non TATA but I.S	1131.6 Mtr.	₹	96.80	₹ 1,09,538.88
28	Supply of galvanised iron socket with I.S	1886 Each	₹	15.00	₹ 28,290.00
29	Supply of G.I. short piece of non TATA b	3772 Each	₹	36.80	₹ 1,38,809.60
30	Supply of G.I. plain equal elbow of apprc	1886 Each	₹	16.00	₹ 30,176.00
31	f) Saddle piece	1886 Each	₹	85.50	₹ 1,61,253.00
Total Amount=					₹ 50,66,412.21
Add GST @18%=					₹ 9,11,954.20
Total incl. GST=					₹ 59,78,366.41
Add L.W.Cess @1%=					₹ 59,783.66
Total incl. GST & L.W.Cess=					₹ 60,38,150.07
Add Contingency @3% on Total incl. GST=					₹ 1,79,350.99
Grand Total=					₹ 62,17,501.07
Say, ₹					₹ 62,17,501.00

(In Words Rupees SixtyTwo Lakh(s) Seventeen Thousand Five Hundred One Only)

**JUNIOR ENGINEER
SUB-DIVISION/DIVISION
P.H. ENGINEERING DTE.**

**ASSISTANT ENGINEER
SUB-DIVISION/DIVISION
P.H. ENGINEERING DTE.**